PPS-BLT-U10 - Source Interface Summary

Supplier table envelope / source KD2101L / reviewed 2026-11-16

NOT TO SCALE. This summary preserves supplier labels and their scope. It is not a manufacturing drawing, CAD file, fit approval or pressure rating.

All dimensions are millimetres unless stated. Drawing views are separate alternatives; do not merge their spans, electrical forms or clearance assumptions.

View / option	Supplier table outline

Outstanding acceptance information

1. The listed outline does not define sensing-element position, immersion termination or dimensional datums.

2. Confirm the line-suspension fixture, handling loads, immersion/depth/medium limits and sealing of the exact assembly.

3. Confirm the integral BNC cable and its termination/strain relief; the source does not establish a threaded pressure port or connector pin-number drawing.

Source and document request

KD2101L supplier catalogue

https://www.yzkds.com/product/847.html
Request the approved 2D drawing, STEP if available, connector/pinout and required calibration/response records. Availability and exact scope are confirmed with the offered variant.

Supplier table outline

Supplier-listed outline	Dia 12x200 mm
Mechanical installation label	Line suspension
Electrical output label	Integral BNC output

Scope: Dia explicitly denotes a diameter. The second value is conventionally interpreted as axial outline length; the supplier table does not define dimension reference planes, maximum envelope, thread/connector inclusion or tolerances.

Mechanical: Line suspension; no pressure-port thread listed

Electrical: Integral BNC output cable; immersion limits and termination to confirm

Cable: 5 m shielded cable; source end labels integral BNC output

Source locator: .product-detail-tabcon table:nth-of-type(1) > tbody > tr:nth-of-type(19) > td:nth-of-type(3)

Request review of this interface and its approved drawing

No schematic clearance, seal, thread engagement or thermal/pressure rating is inferred from this reference. Supply the customer port and available installation space for review.